



भारतीय सूचना प्रौद्योगिकी संस्थान गुवाहाटी
Indian Institute of Information Technology Guwahati

Dept./Section/Centre: Works Section

Ref: NIQ No. IIITG/Works/40/2023/125

Date:21.06.2023

To,

Interested Vendors/Contractors

Sub: Notice Inviting Quotation (NIQ) for Dismantling of class room partition wall & making of ceiling and floor tiles and making of 2 nos caretaker room in Admin & Acd Building at IIIT Guwahati campus.

Dear Sir,

The undersigned invites sealed quotations from the local vendors/contractors for onward submission along with requisite documents for the work "Dismantling of class room partition wall & making of ceiling and floor tiles and making of 2 nos caretaker room in Admin & Acd Building at IIIT Guwahati campus". in the form of BOQ (Bill of Quantities).

Sl No.	Particulars	Details of Works
1	Name of Works	Dismantling of class room partition wall & making of ceiling and floor tiles and making of 2 nos caretaker room in Admin & Acd Building at IIIT Guwahati campus.
2	Completion period	15 days
3	Last Date & Time of Submission of BOQ	28.06.2023 up to 2.30 pm
4	Date & Time of opening	28.06.2023 at 3.30 pm
5	Scope of work	As detailed in the BOQ
6	SD money	3% will be deducted which will be released after 6 months from the date of completion.

You are requested to submit your rates in the given BOQ format (with your working rates in the rate's column) with the proof of following documents.

TERMS & CONDITIONS:

1.The bidder must have a valid Govt./Semi Govt. contracting registration with working experience of successfully completed similar works during the last seven years ending previous day of last date of submission of tender as under:

**Three similar completed works costing each not less than ₹0.63 Lakh, or
Two similar completed works, each of value not less than ₹ 0.95Lakh, or
One similar completed work of value not less than ₹1.28 lakh.**

2.The Bidder should have GSTN, PAN and own Bank Account.

3.Other terms & Condition will be as per IIITG rule.

4. The rates Quoted by the bidder shall be inclusive of GST, other statutory taxes/cess/royalties as may be applicable.

Sd/-
Associate Dean (Admin)

BOQ Format

Sl. No.	Description Of Item	Unit	Qty	Rate	Amount(₹)
1	Specification – for waterproofing of Over Head Water Tank Surface Preparation: Preparing the surface by cleaning & chipping the surface for removing loose, laitance etc. All the construction joints should be cut in a Groove and wash the entire surface thoroughly by water making the Surface saturated dry condition and filling the gaps with polymer modified mortar followed by epoxy bonding agent	sqm	77		
2	Coating Application: Application of one coat of polymer modified coating Asian MPP over the entire prepared surface by mixing cement and polymer in a ratio 1:1.5 (1 polymer: 1.5 Cement). Followed by polymer modified mortar. Application of two coats of Demp block-2K (Two Component Cementitious coating) over the base coat. Sprinkle fine sand over the coated area (when the coating is green) and let dry for 72Hr. (Air Cure)	sqm	77		
3	20 mm thick plastering with cement mortar 1:3 (1 cement: 3 Sand) over the water proofing treatment area admixed with Sylo 200 (@ 200 ml per bag of cement.)	sqm	77		
Total (₹)					
Add GST@____%					
Grand Total					