



भारतीय सूचना प्रौद्योगिकी संस्थान गुवाहाटी
Indian Institute of Information Technology Guwahati

Dept./Section/Centre: Works

Ref: NIQ No.IITG/Works/2024-25/252

Date: 16.01.2025

To,

Interested Vendors/Contractors

Sub: Notice Inviting Quotation (NIQ) for Making of Cattle proof gate in the Newly developed lawn and railing in corridor over parapet wall of class room at IIT Guwahati campus.

Dear Sir,

The undersigned invites sealed quotations from the local vendors/contractors for onward submission along with requisite documents for the work "Making of Cattle proof gate in the Newly developed lawn and railing in corridor over parapet wall of class room at IIT Guwahati campus in the form of BOQ (Bill of Quantities) enclosed herewith.

SI No.	Particulars	Details of Works
1	Name of Works	Making of Cattle proof gate in the Newly developed lawn and railing in corridor over parapet wall of class room at IIT Guwahati campus.
2	Completion period	25 days
3	Last Date & Time of Submission of BOQ	28.01.2025 up to 2.30 pm
4	Date & Time of opening	28.01.2025 at 3.30 pm
5	Scope of work	As detailed in the BOQ
6	SD money	3% will be deducted which will be released after 6 months from the date of completion.

You are requested to submit your rates in the given BOQ format (with your working rates in the rate's column) with the proof of following documents.

TERMS & CONDITIONS:

1.The bidder must have a valid Govt./Semi Govt. contracting registration with working experience of successfully completed similar works during the last seven years ending pervious day of last date of submission of tender as under

Three similar completed works costing each not less than ₹ 0.68 Lakh, or

Two similar completed works, each of value not less than ₹ 1.02 Lakh, or

One similar completed work of value not less than ₹ 1.36 lakh.

Similar works shall mean Completed Civil works of required values as above in last 7 years.

2.The Bidder should have GSTN, PAN and own Bank Account.

3.Other terms & Condition will be as per IITG rule.

4. The rates Quoted by the bidder shall be inclusive of GST, other statutory taxes/cess/royalties as may be applicable.

Dean Administration

IIT Guwahati
Bongora, Guwahati- 781015

BOQ

Name of work : Making of Cattle proof Gate in the newly developed Lawn and railing in corridor over parapet wall of class room at IIIT Guwahati campus.

SL No	Discription of works	Unit	Qty.	Rate	Amount (Rs)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.	cum	3.942		
	All kinds of soil				
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level (1 cement : 3coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	1.248		
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	836.940		
4	Centering and shuttering including strutting, propping etc. and removal of form for all heights Foundations, footings, bases of columns, etc. for mass concrete	Sqm	15.120		
5	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	Sqm	10.800		
6	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm)	Sqm	10.800		
7	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work .	Sqm	24.157		
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. 5.22 A.6 Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	142.564		
9	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:1½:3 (1 cement : 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	1.674		
	TOTAL=				