



भारतीय सूचना प्रौद्योगिकी संस्थान गुवाहाटी
INDIAN INSTITUTE OF INFORMATION TECHNOLOGY GUWAHATI
Bongora, Kamrup (R), Assam, India, PIN 781015

Phone: +91-361-2801091
email: doa@iiitg.ac.in

Notice Inviting Quotation

NIQNo.IIITG/Works/2024-25/282 dated: 10.07.2025

To,

Interested Vendors/Contractors

The undersigned invites sealed quotations from the vendors/contractors for onward submission along with requisite documents for the work Renovation of front portion of Admin cum Acad building of IIIT Guwahati campus in the form of BOQ (Bill of Quantities) enclosed herewith.

Sl No.	Particulars	Details of Works
1	Name of Works	Renovation of front portion of Admin cum Acad building of IIIT Guwahati campus.
2	Completion period	30 days from the date of issue of work order
3	Last Date & Time of Submission of BOQ	21.07.2025 up to 3.00 pm
4	Date & Time of opening	21.07.2025 at 3.30 pm
5	Scope of work	As detailed in the BOQ
6	SD money	2.5% will be deducted which will be released after 3 months from the date of completion.

You are requested to submit your rates in the given BOQ format (with your working rates in the rate's column) with the proof of following documents.

TERMS & CONDITIONS:

1. The bidder must have a valid Govt./Semi Govt. contracting registration with working experience of civil works of value not less than Rs. 1,00,000/-
2. The Bidder should have valid GSTN, PAN and own Bank Account and must be a business entity of the state of Assam.
3. All other general Terms & conditions as followed in IIITG for works will also apply in this NIQ.
4. The rates Quoted by the bidder shall be inclusive of GST, other statutory taxes/cess/royalties as may be applicable.
5. The bidder quoting the lowest amount will be awarded the work. However, if the Institute discover that the price quoted by a Bidder/Company/Firm/Agency is abnormally low or unjustified, the bid may not be considered.
6. Hard copies of Bid along with all other required documents must be submitted to the office of IIIT Guwahati, Bongora, Kamrup(R), Assam-781015, India on or before 3 pm of 21.07.2025

(Signature)
10/07/2025
Dean Administration

BOQ

**Name of work: Renovation of front portion of Admin cum Acad building of IIIT
Guwahati campus**

Sl No	Description of work	Unit	Qty	Rate	Amount
1	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete: Granite stone slab of colour black, Cherry/Ruby red, Area of slab over 0.50 sq	Sqm	33.86		
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	Sqm	558.08		
3	Providing and applying cement base damp proof putty/plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	Sqm	112.00		
4	Finishing walls with textured exterior paint of required shade : Old work (Two or more coats on existing cement paint surface applied @ 3.28 ltr/10 sqm	Sqm	304.70		
5	Finishing walls with water proofing cement paint of required shade : 13.109.1 Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litres/10 sqm complete including cost of Priming coat.	Sqm	253.38		
6	Scaffolding for additional height of front porch about 8-9 metre	Job	1		
				TOTAL	