



भारतीय सूचना प्रौद्योगिकी संस्थान गुवाहाटी  
Indian Institute of Information Technology Guwahati

Dept./Section/Centre: Works

File NIQ No. IIITG/Works/2025-26

Date: 16.01.2026

To,

**Interested Vendors/Contractors**

**Sub:** Notice Inviting Quotation (NIQ) Development of out side space adjacent to the Boys hostel kitchen and utensil cleaning area at IIIT Guwahati Campus.

Dear Sir,

The undersigned invites sealed quotations from the local vendors/contractors for onward submission along with requisite documents for the work Development of out side space adjacent to the Boys hostel kitchen and utensil cleaning area at IIIT Guwahati Campus. the form of BOQ (Bill of Quantities) enclosed herewith.

SI No.	Particulars	Details of Works
1	Name of Works	“Development of out side space adjacent to the Boys hostel kitchen and utensil cleaning area at IIIT Guwahati Campus.”
2	Completion period	15 days from the date of issue of work order
3	Last Date & Time of Submission of BOQ	23.01.2026 up to 2.30 pm
4	Date & Time of opening	23.01.2026 at 3.30 pm
5	Scope of work	As detailed in the BOQ
6	SD money	2.5% will be deducted which will be released after 3 months from the date of completion.

You are requested to submit your rates in the given BOQ format (with your working rates in the rate's column) with the proof of following documents.

**TERMS & CONDITIONS:**

1. The bidder must have a valid Govt./Semi Govt. contracting registration with working experience of civil works of value not less than Rs. 50,000/-
2. The Bidder should have GSTN, PAN and own Bank Account.
3. Other terms & Condition will be as per IIITG rule.
4. The rates Quoted by the bidder shall be inclusive of GST, other statutory taxes/cess/royalties as may be applicable.

*Open for Bidding  
19/01/2026*  
Dean Administration

**BOQ**

**Name of work: Development of out side space adjucent to the Boys hostel kitchen and utensil cleaning aera at IIIT Guwahati Campus.**

<b>Sl No</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate(Rs)</b>	<b>Amount(Rs)</b>
1	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.	Sqm		<b>116.00</b>	
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in : cement mortar 1:4 (1 cement : 4 coarse sand)	Sqm		<b>3.36</b>	
<b>Total Amount</b>					