



भारतीय सूचना प्रौद्योगिकी संस्थान गुवाहाटी
Indian Institute of Information Technology Guwahati

Dept./Section/Centre: Works

File NIQ No. IIITG/Works/2025-26

Date:04.03.2026

To,

Interested Vendors/Contractors

Sub: Notice Inviting Quotation (NIQ) "Dressing of earth for proposed football field, near volleyball court and minor earth filling in between SAC and Girls hostel and making of fencing in front of SAC building at IIITG Campus".

Dear Sir,

The undersigned invites sealed quotations from the local vendors/contractors for onward submission along with requisite documents for the work "Dressing of earth for proposed football field, near volleyball court and minor earth filling in between SAC and Girls hostel and making of fencing in front of SAC building at IIITG Campus".
the form of BOQ (Bill of Quantities) enclosed herewith.

SI No.	Particulars	Details of Works
1	Name of Works	"Dressing of earth for proposed football field, near volleyball court and minor earth filling in between SAC and Girls hostel and making of fencing in front of SAC building at IIITG Campus".
2	Completion period	20 days from the date of issue of work order
3	Last Date & Time of Submission of BOQ	10.03.2026 up to 2.30 pm
4	Date & Time of opening	10.03.2026 at 3.30 pm
5	Scope of work	As detailed in the BOQ
6	SD money	2.5% will be deducted which will be released after 3 months from the date of completion.

You are requested to submit your rates in the given BOQ format (with your working rates in the rate's column) with the proof of following documents.

TERMS & CONDITIONS:

- 1.The bidder must have a valid Govt./Semi Govt. contracting registration with working experience of waterproofing works in RCC building of value not less than Rs. 1,00000/-
- 2.The Bidder should have GSTN, PAN and own Bank Account.
- 3.Other terms & Condition will be as per IIITG rule.
4. The rates Quoted by the bidder shall be inclusive of GST, other statutory taxes/cess/royalties as may be applicable.


04/03/2026
Dean Administration

BOQ

Name of work : Dressing of earth for proposed football field, near volleyball court and minor earth filling in between SAC and Girls hostel and making of fencing in front of SAC building at IIITG Campus.

SL No	Description of works	Unit	Qty.	Rate	Amount (Rs)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.	cum	7.68		
	All kinds of soil				
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	0.25		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	cum	2.65		
4	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement. : 12 mm cement plaster	Sqm	18.67		
5	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 75x75 mm excluding strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. :				
	height 1.2 mtr mesh size 75mmx75mm (medium)	Roll	15.00		
6	Bamboo	Nos	25.00		
7	GI binding wire	kg	30.00		
8	Labour for fixing of fencing	Nos	12.00		
9	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.	Sqm	6.25		
10	Labour for earth dressing work	Nos	20		
11	supplying and filling of local earth	Cum	100		
12	JCB for leveling purpose	Hour	2		
			Total Amount =		