



भारतीय सूचना प्रौद्योगिकी संस्थान गुवाहाटी  
Indian Institute of Information Technology Guwahati

Dept./Section/Centre: Works

File NIQ No. IIITG/Works/2025-26 /324

Date:13.04.2026

To,

Interested Vendors/Contractors

**Sub:** Notice Inviting Quotation (NIQ: "Providing and laying of Hume pipe culvert, repairing of security barrack-2 & fixing of Granite strip at boy's hostel at IIIT Guwahati campus."  
**Dear Sir,**


The undersigned invites sealed quotations from the local vendors/contractors for onward submission along with requisite documents for the work "Providing and laying of Hume pipe culvert, repairing of security barrack-2 & fixing of Granite strip at boy's hostel at IIIT Guwahati campus." the form of BOQ (Bill of Quantities) enclosed herewith.

SI No.	Particulars	Details of Works
1	Name of Works	"Providing and laying of Hume pipe culvert, repairing of security barrack-2 & fixing of Granite strip at boy's hostel at IIIT Guwahati campus."
2	Completion period	20 days from the date of issue of work order
3	Last Date & Time of Submission of BOQ	27.04.2026 up to 2.30 pm
4	Date & Time of opening	27.04.2026 at 3.30 pm
5	Scope of work	As detailed in the BOQ
6	SD money	2.5% will be deducted which will be released after 3 months from the date of completion.

You are requested to submit your rates in the given BOQ format (with your working rates in the rate's column) with the proof of following documents.

**TERMS & CONDITIONS:**

- 1.The bidder must have a valid Govt./Semi Govt. contracting registration with working experience of Civil work of value not less than Rs. 1,00000/-
- 2.The Bidder should have GSTN, PAN and own Bank Account.
- 3.Other terms & Condition will be as per IIITG rule.
4. The rates Quoted by the bidder shall be inclusive of GST, other statutory taxes/cess/royalties as may be applicable.

  
13/04/2026  
Dean Administration

## BOQ

**Name of work : Providing and laying of Hume pipe culvert, repairing of security barrack-2 & fixing of Granite strip at boy's hostel at IIT Guwahati campus.**

SL NO	Discription of works	Unit	Qty.	Rate	Amount (Rs)
1	Excavator charges for earth cutting and other related works	Hour	2.00		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	2.59		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	cum	1.10		
4	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement. : 12 mm cement plaster	Sqm	7.00		
5	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete				
	450 mm dia RCC pipes. 10 mtr (4 nos)	Mtr	10.00		
6	Supplying and stacking at site.				
	53 mm to 22.4 mm size stone aggregate	Cum	1.80		
7	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density	Cum	1.50		
8	Bamboo For Security Barrack 2 repairing	Nos	30		
9	Tarpaulins For Security Barrack 2 repairing	Sqft	7		
10	Labour For Security Barrack 2 repairing	Nos	15		
11	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.				
	Polished Granite stone slab colour of Black, Cherry/Ruby Red or equivalent .	Sqm	1.6		
<b>Total Amount</b>					