



भारतीय सूचना प्रौद्योगिकी संस्थान गुवाहाटी  
Indian Institute of Information Technology Guwahati

Dept./Section/Centre: Works

Ref.: NIQ No. IIITG/Works/2026-27/ 336

Date: 04.08.2026

To,

Interested Vendors/Contractors

**Sub:** Notice Inviting Quotation (NIQ: Repainting of damage portion of toilets and room in all floors and wall tiles fixing at utensil area at Boys hostel and ciling repairing at Annexure I & II and Admin building at IIIT Guwahati Campus.

**Dear Sir,**


The undersigned invites sealed quotations from the local vendors/contractors for onward submission along with requisite documents for the work: Repainting of damage portion of toilets and room in all floors and wall tiles fixing at utensil area at Boys hostel and ciling repairing at Annexure I & II and Admin building at IIIT Guwahati Campus. the form of BOQ (Bill of Quantities) enclosed herewith.

| SI No. | Particulars                           | Details of Works                                                                                                                                                                                        |
|--------|---------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1      | Name of Works                         | Repainting of damage portion of toilets and room in all floors and wall tiles fixing at utensil area at Boys hostel and ciling repairing at Annexure I & II and Admin building at IIIT Guwahati Campus. |
| 2      | Completion period                     | 7 days from the date of issue of work order                                                                                                                                                             |
| 3      | Last Date & Time of Submission of BOQ | 10.08.2026 up to 2.30 pm                                                                                                                                                                                |
| 4      | Date & Time of opening                | 10.08.2026 at 3.30 pm                                                                                                                                                                                   |
| 5      | Scope of work                         | As detailed in the BOQ                                                                                                                                                                                  |
| 6      | SD money                              | 2.5% will be deducted which will be released after 3 months from the date of completion.                                                                                                                |

You are requested to submit your rates in the given BOQ format (with your working rates in the rate's column) with the proof of following documents.

**TERMS & CONDITIONS:**

1. The bidder must have a valid Govt./Semi Govt. contracting registration with working experience of Civil work of value not less than Rs. 80,000/-
2. The Bidder should have GSTN, PAN and own Bank Account.
3. Other terms & Condition will be as per IIITG rule.
4. The rates Quoted by the bidder shall be inclusive of GST, other statutory taxes/cess/royalties as may be applicable.

  
Dean Administration

## BOQ

**Name Of Work: Repainting of damage portion of toilets and room in all floors and wll tiles fixing at utensil area at Boys hostel and ciling repairing at Annexure I & II and Admin building at IIIT Guwahati Campus.**

| Sl.no | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Unit | Qty    | Rate | Amount |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------|------|--------|
| 1     | Distempering with 1st quality acrylic distember (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade : Old work (one or more coats                                                                                                                                                                                                                                                                                                                        | Sqm  | 225.00 |      |        |
| 2     | Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.                                                                                                                                                                                                                                                                                                                       | Sqm  | 91.41  |      |        |
| 3     | Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound ) content.                                                                                                                                                                                                                                                                                                                                                                                            |      |        |      |        |
|       | With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre                                                                                                                                                                                                                                                                                                                                                                                                                        | Sqm  | 91.41  |      |        |
| 4     | Dame stop                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Ltr  | 8.00   |      |        |
| 5     | 2x2 ciling bord                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Box  | 3.00   |      |        |
| 6     | Gypsum bord                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Nos  | 3.00   |      |        |
| 7     | Mason for ciling repairing                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Nos  | 5.00   |      |        |
| 8     | Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. | Sqm  | 36.00  |      |        |
| 9     | Cement Concrate flooring (materil & labour)                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Job  | 1.00   |      |        |
|       | <b>TOTAL AMOUNT</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |      |        |      |        |