



भारतीय सूचना प्रौद्योगिकी संस्थान गुवाहाटी

Indian Institute of Information Technology Guwahati

Dept./Section/Centre: Works Section

Ref: NIQ No. IIITG/Works/2022-23/38/116

Date:03.05.2023

To,  
Interested Vendors/Contractors

**Sub:** Notice Inviting Quotation (NIQ) for Shifting of garbage storage shed near Boys hostel and placing of Hume pipe (600mm dia) culvert near Faculty Building and Gate No.2 at IIIT Guwahati campus  
**Dear Sir,**


The undersigned invites sealed quotations from the local vendors/contractors for onward submission along with requisite documents for the work Shifting of garbage storage shed near Boys hostel and placing of Hume pipe (600mm dia) culvert near Faculty Building and Gate No.2 at IIIT Guwahati campus in the form of BOQ (Bill of Quantities) to be collected from this office.

Sl No.	Particulars	Details of Works
1	Name of Works	Shifting of garbage storage shed near Boys hostel and placing of Hume pipe (600mm dia) culvert near Faculty Building and Gate No.2 at IIIT Guwahati campus
2	Completion period	30 days
3	Last Date & Time of Submission of BOQ	10.05.2023 up to 2.30 pm
4	Date & Time of opening	10.05.2023 at 3.30 pm
5	Scope of work	As detailed in the BOQ
6	SD money	3% will be deducted which will be released after 3 months from the date of completion.

You are requested to submit your rates in the given BOQ format (with your working rates in the rate's column) for further necessary action at this end. The BOQ form may be collected from the IIITG office by submitting proof of documents mentioned in following terms & conditions.

**TERMS & CONDITIONS:**

1. The bidder must be having valid Govt./Semi Govt. contracting registration with working experience of **civil works of value not less than 1 Lakh.**
2. The Bidder should have GSTN, PAN and own Bank Account.
3. Other terms & Condition will be as per IIITG rule.
4. The rates Quoted by the bidder shall be inclusive of GST. other statutory taxes/cess/royalties as may be applicable.

  
Associate Dean Administration



**BOQ**

**Name of work : Shifting of garbage storage shed near Boys hostel and placing of Hume pipe (600mm dia) culvert near Faculty Building and Gate No.2 at IIT Guwahati campus**

SL No	Description of works	Unit	Qty.	Rate	Amount (Rs)
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	2.80		
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement :4 coarse sand)	sqm	14.00		
3	12 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)	Sqm	30.00		
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	cum	80.00		
5	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm	sqm	16.00		
6	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg	249.00		
7	Finishing walls with water proofing cement paint of required shade				
	New work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	28.00		
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
	Two or more coats on new work				
	600 mm dia RCC pipes.	sqm	14.80		
9	Providing flat brick soling under foundation, including packing with coarse sand and watering etc complete as directed with bricks class designation-75 in cement mortar in proportion 1:4 including curing complete as specified and as directed.	sqm	28.00		
10	Labour for dismantling of existing garbage shed and re fixing near by as shown at site				
	Unskilled Labour	No	10.00		
	Skilled Labour	No	5.00		
11	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete				
	600 mm dia RCC pipes.	mtr	22.50		
			<b>Total</b>		
			<b>Rebate if any</b>		
			<b>Grand Total</b>		